

1000KVA AC/DC MOTOR TEST SYSTEM




Nexjen Electric Motor Test Systems are built on the principle of safe, simple operation and dependable service. The same Jenkins test transformer design we have used for the past fifty years sits at the core of a power supply engineered to perform continuously at full ratings for 8 hours. With heavy duty components and very few moving parts, the Nexjen Electric Motor Test System is designed to operate for decades without maintenance.

While the power circuit in our electric motor test systems has remained unchanged, the control and management capabilities of the system, incorporated the latest in industrial software technology. A PLC handles the control logic in each system, reducing the number of components and increasing both the reliability and flexibility of the system. Our PC based test documentation system records and displays power, vibration, temperature and dynamometer information during motor tests.

MOTOR TEST SYSTEM SPECIFICATION	NS
MODEL	1000KVA AC/DC
MODEL #	S1000MV480ACDC
SYSTEM REQUIREMENTS	
PHYSICAL SPACE REQUIRED	78H X 120W X 72D
ELECTRICAL INPUT (60HZ)	480V 1250A
PLC-BASED SYSTEM CONTROL	
RELIABLE, REPEATABLE SYSTEM CONTR	OL
SIMPLE, PROGRAMMATIC CONTROL AD	DJUSTMENTS
REAL-TIME SYSTEM STATUS TO TDS SOF	TWARE
REMOTE/ETHERNET ACCESS FOR SYSTE	M TROUBLESHOOTING
AC SUPPLY	
MAX AC CURRENT OUTPUT	120V 1200A
MAX AC VOLTAGE OUTPUT	4200V 137A
STANDARD AC VOLTAGE TAPS	120,240,480,600,1200,2400,4200
OPTIONAL AC VOLTAGE TAP	7200V
PERCENTAGE ADJUSTMENTS FOR	50%, 60%, 70%, 80%, 90%,
EACH VOLTAGE TAP	110%, 115%
SOFT STARTING	STANDARD
FULL VOLTAGE STARTING	STANDARD
CURRENT LIMIT PROTECTION	4 LEVELS
AUXILIARY AC SUPPLY	(3 PHASE, VARIABLE FROM 0 TO MAX OUTPUT)
MAX AUXILIARY AC OUTPUT	560V 35A
CURRENT LIMIT PROTECTION	1 LEVEL
DC FIELD SUPPLY	(VARIABLE FROM 0 TO MAX OUTPUT)
MAX FIELD OUTPUT	500V 35A
FIELD LOSS PROTECTION	1 LEVEL
TEMPORARY BYPASS	STANDARD
CURRENT LIMIT PROTECTION	STANDARD
DC ARMATURE SUPPLY	(VARIABLE FROM 0 TO TAP SETTING)
MAX ARMATURE OUTPUT CURRENT	450A
STANDARD DC ARMATURE VOLTAGE RANGES	40, 80, 160, 320, 585
CURRENT LIMIT PROTECTION	4 LEVELS
OPTIONAL SYNCHRONOUS DC ARMAT	JRE SUPPLY
SIZING AND PRICE DETERMINED BY CU	STOMER TEST REQUIREMENTS
TEST DOCUMENTATION SPECIFICATI	ONS
SOFTWARE	HARDWARE
BASE PACKAGE (STANDARD)	
AC/DC METER DISPLAY	PC AND MONITOR
NAMEPLATE DATA ENTRY	REPORT PRINTER
REPORT GENERATION	SIDE MOUNTING
TEST HISTORY LOOKUP	
TEMPERATURE & VIBRATION MODULE (OPTIONAL)
NOMINAL METER DISPLAY	TEMP AND VIBE MODULE
TEMP VS. TIME CURVES	4 THERMOCOUPLE INPUTS
VIBRATION FFT GRAPHS	4 RTD INPUTS
CHANNEL CONFIGURATION	6 ACCELEROMETER INPUTS
TEMP AND VIBE REPORTS	ACCELEROMETERS INCLUDED
DYNAMOMETER INTERFACE (STAND	ARD)
HORSEPOWER / KW	USB OR SERIAL INTERFACE
% EFFICIENCY / TORQUE (ft/lb.)	CONFIGURED FOR AW DYNOS
RPM AND % LOAD	USE EXISTING DYNO

1000KVA MOTOR TEST SUPPLY

The 1000KVA Motor Test Supply will run most 1000HP AC motors at full load and most 3500HP motors at no lead. (AC motors typically draw 25-35% of full load amps with no load). The DC supply will run most 1000HP DC motors at full load, and will start and run most DC motors at no load.



- Engineered for full-capacity AC and DC outputs at rated current for 8 hours.
- Motor starting by current limited Soft starter or with fullvoltage tap adjustments.
- Independent, variable-voltage adjustment on DC Field and Armature Supplies.
- Simple, push-button operation with intuitive controls, clear indicators and LED meters.
- Industrial PLC provides reliable control, real-time system status, simple logic adjustments and remote troubleshooting.
- Operator and System Safeties; E-stop, overload protection, trips and electrical interlocks.
- Transformer Powered by Jenkins Electric Company.



SOFTWARE

STANDARD TEST DOCUMENTATION PACKAGE

The standard Test Documentation Package ships with a PC and Printer, displays real-time AC and DC meter data during tests, records data to a searchable test database and prints a test report to be kept on file and/or provided to the client. (Test reports can be directly saved to ACS job folders).

System Idle	State: Mile Date: Fri, Jan 19, 2013 Time: 111805.AB	%nexjen	ABC Motor Repa Motor Test Cent		Total Test: 40:00:30 Elapse-C: 40:00:30 Ramalming: 40:00:30	-
Trips	Customer Name			Job Runber		
-	Low AC You Rated =	AC Amps Rated +		Abut Pewer ted = 250	RPU Rated = 1800	ACINA
38.0	u <mark>4</mark>	83 24		249	1786	DC Me
Tap Switches	L2 4	79 23		94.2	99.6	Dut
Al Los Voltage In Practice	L3 4	80 23	7 Thermocoupie	RTD E Osering (7)	Workson 00E Bearing(11)	Pro
Al Mel Yalay In Fection Di Ara Yalay 10	Input Power			125	119	
Variable Supply	197	.2 0.8		112	Sator housing (F)	

	480	Motor C	ter Amps: Fid Am	2	lodel No: 40	Job No: 1098-76 Serial N		145 15334444					
HP:	250		KW:	· ·	86.5	RPM:	190	10					
	101(2),	RTD2+P	(102(7)	PCIDG#P	(103(-7),	RTD4=RTD	4(T)						
Date	Time	TCI	102	753	764	NT01	(HTD2	(MTEO	NTD4	11	N2	3/8	
Date 6/14/0012	12 40 22 P	141	7.20	109	202	212	1114	115	218	0.157	6.183	0.314	- 6
Dule 6/14/2013 6/14/2013	12.40.22 P	121	120	108	901	313	114	115	218	0.157	6.183	0.314	0.0
Date 6/14/2013 6/14/2013	12.40.22 P 12.40.24 P 12.40.25 P	121	120 128 128	108	901 901 901	513 513 513	114	125	118	8.197 8.197 8.197	6 183 6 183 6 183	0.314 0.314 0.314	0.0.0
Dule 6/14/2013 6/14/2013	12 40 22 P 12 40 25 P 12 40 25 P 12 40 25 P	121	-30 -30 -30 -30	108	901 901 901	313	114	115	218	0.157	6.183	0.314	20.0.0.0.0
Date 6/14/0013 6/14/0013 6/14/0013	12.40.22 P 12.40.24 P 12.40.25 P	121 121 121	120 128 128 128	108 108 108 108 108	101 101 101 101	813 813 814 814	154 154 154	125 125 125 125	10	8.157 8.157 8.157 8.157	6 183 6 183 6 183 6 183	0314 0314 0314 0314	0.0.0.0.0
Date 6/14/0013 6/14/0013 6/14/0013 6/14/0013	12 40 22 P 12 40 24 P 12 40 25 P 12 40 25 P 12 40 25 P	121 121 121 121	-30 -30 -30 -30	108 108 108	901 901 901	10 10 10 10	114 114 114 114	125 125 125 125 125	1 1 1	8.157 8.157 8.157 8.157 8.157	6 183 6 183 6 183 6 183 6 183	0.314 0.314 0.314 0.314 0.314	0.0.0.0.0
Date 614(2013) 614(2013) 614(2013) 614(2013) 614(2013) 614(2013)	12 40 22 P 12 40 25 P 12 40 25 P 12 40 25 P 12 40 25 P 12 40 20 P	121 121 121 121 121	120 136 136 136 130 120	108 108 108 108 109	701 501 501 701 701	010 110 110 110 110	114 114 114 114 114	125 125 125 125 125 125	1 1 1	8.157 8.167 8.167 8.167 8.157	6 180 6 180 6 180 6 180 6 180 6 180	0.314 0.314 0.314 0.314 0.314 0.314	0.0.0.0

UPGRADES & ACCESSORIES

- Auxiliary AC Supply
- Higher Voltage up to 7200
- Synchronous Motor Start

- Fields up to 70 Amps
- **TEMP AND VIBE MODULE**

The Temp and Vibe Module is a portable data acquisition system that connects to the Test Documentation PC via a USB cable. It includes ports for 6 Accelerometers (sensors included), 4 Thermocouples and 4 RTDs. The software upgrade includes the display of Temperature and Vibration data on the meter screen, and graphical display of temperature vs. time curves and vibration fft's. (Optional)





LEAD ISOLATOR BOX

The Lead Isolator Box provides a safe method for isolating the connections between motor leads and test system leads. Fabricated from nonconductive material, the Lead Isolator Box keeps test operators safe from arching between lead connections. (Standard)

BOOM MOUNTED TEST LEADS

The boom mounted test leads provides a safe method for keeping leads out of the way while motors are being tested. (Optional)

DYNAMOMETER INPUT

With a simple connection to an AW Dynamometer Controller the Test Documentation Software displays and records mechanical test data including output power, RPM, % efficiency, and % load and torque. Configuration for non-AW Dynamometers is available and quoted separately. (Standard)